

55 Park Slope Clifton, NJ 07011

Ph: +1-201-321-8506

Fax: +1-201-624-7007

www.AccessRec.com

Modular Walkways & Decks with Narrow Spacing (1/2")

Approximate Weight per Running FT.

		Approximate Weight per Running Ft.			
	-	3'	4'	5'	6'
		<u>Wide</u>	Wide	Wide	Wide
Roll Outs (assembled w/ nylon rope):					
- PT - 5/4x (w/o connectors)		9.8	13.1	Not Offered	
- PT - 5/4x (w/ connectors)		9.8	13.1	Not Offered	
- TREX - 5/4x (w/o connectors)		13.7	18.3	22.9	27.4
- TREX - 5/4x (w/ connectors)		13.7	18.3	22.9	27.4
- Teak/IPE - 1x (w/o connectors)		10.8	14.4	18.0	21.6
- Teak/IPE - 1x (w/ connectors)		10.8	14.4	18.0	21.6
- Teak/IPE - 5/4x (w/ connectors)		12.7	17.0	21.2	25.4
Deck Kits (built on 2x PT "sleepers"):					
- PT - 5/4x (w/o connectors)		13.5	18.0	22.5	27.0
- PT - 5/4x (w/ connectors)		13.5	18.0	22.5	27.0
- TREX - 5/4x (w/ connectors)		17.4	23.2	29.0	34.8
- Teak/IPE - 1x (w/ connectors)		14.5	19.3	24.1	29.0
Deck Kits (built on 2x4 PT frames):					
- PT - 5/4x		18.5	24.6	30.8	36.9
- TREX - 5/4x		26.1	34.8	43.5	52.1
- Teak/IPE - 1x		19.4	25.9	32.4	38.9
Deck Kits (built on on 2x6 PT Frames):					
- PT - 5/4x		21.1	28.1	35.1	42.1
- TREX - 5/4x		25.0	33.3	41.7	50.0
- Teak/IPE - 1x		22.1	29.4	36.8	44.1
Flex Walk (assembled w/ Stainless Steel Rods):	:				
- PT - 5/4x (w/ connectors)		10.0	13.3	16.7	20.0
- TREX - 2x (w/ connectors)		18.0	24.0	30.0	36.0
- TREX - 5/4x (PT Reinforced) (w/ connectors)		28.6	38.1	47.7	57.2
- Teak/IPE - (w/ connectors)	5/4" x:	13.0	17.3	21.7	26.0
	2"x:	19.5	26.0	32.5	39.0

PT: Pressure Treated Southern Pine (non-arsenic deck lumber).

TREX: Plastic & Wood Composite Decking.

Teak/IPE: A very durable South American hardwood similar to Teak.

Walkways with No Spacing: Add 20%.